

STATE OF KANSAS
STATE CORPORATION COMMISSION


15-047-20515-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Edwards County. Sec. 34 Twp. 25S Rge. 16W E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines

NW NW SW
Lease Owner F. G. Holl, et al
Lease Name Curney "C" 2-34 Well No. 2-34
Office Address 6427 East Kellogg, Wichita, Kansas 67207
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plot

Dry Hole
Date Well completed June 7, 1979 19
Application for plugging filed June 7, 1979 19
Application for plugging approved June 7, 1979 19
Plugging commenced 4:45 PM - June 7, 1979 19
Plugging completed 7:00 PM - June 7, 1979 19
Reason for abandonment of well or producing formation

Dry Hole
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Owen
Producing formation Depth to top Bottom Total Depth of Well 4550'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	123'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud.
Pumped through open end drill pipe
40 sacks at 420' and solid bridge with
plug and 1/2 sack hulls and 12 sacks
to surface. 3 sacks in rathole.
Used 50/50 Pozmix cement.

RECEIVED
STATE CORPORATION COMMISSION
JUN 27 1979
6-27-79
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. A. Wuellner, Secretary
STERLING DRILLING COMPANY
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of June, 19 79.



Charles M. Hall, Notary Public.

My commission expires

15-047-20515-0000

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- CUDNEY "C" 2-34
Located: NW NW SW, Section 34-25S-16W, Edwards County,
Kansas

OWNER: F. G. Holl, et al
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: June 1, 1979
COMPLETED: June 7, 1979

TOTAL DEPTH: 4550'

LOG

0 - 228	Sand and Clay
228 - 259	Sand
259 - 353	Blue Shale
353 - 380	Sand
380 - 426	Shale
426 - 1087	Shale, Sand and Red Bed
1087 - 1099	Anhydrite
1099 - 2055	Shale and Sand
2055 - 4140	Shale and Lime
4140 - 4152	Lime, Shale and Chert
4152 - 4438	Lime, Chert, Sand; Shale and Chert
4438 - 4475	Shale and Chert
4475 - 4550	Shale, Lime and Chert

CASING RECORD

Randl0n joints used 28#, 8 5/8" casing,
410.75' set at 423' K.B. with 325 sacks
60/40 Pozmix with 3% cc. Plug down at
7:15 PM, 6-1-79, by Howco.

RECEIVED
STATE GEOLOGICAL COMMISSION
6-27-79
JUN 27 1979

CONSERVATION DIVISION
DICKENS

Plugged.