


15-047-10039-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Edwards County. Sec. 34 Twp. 25 Rge. 16 (E) W (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW%SW%" or footage from lines C NW NE
Lease Owner Inger Oil Company
Lease Name Giles Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 8-30-62 _____ 19____
Plugging completed 11-30-62 _____ 19____
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Bill Lackamp
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4488 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	407'	None
				5-1/2"	4488'	3743'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 4488', sanded to 4400' and dumped 5 sacks of cement @ 4400' with dump bailer. Pulled 5 1/2" casing. Mudded hole to 310', set rock bridge to 300' and ran 20 sacks of cement @ 300'. Mudded to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

DEC 11 1962

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or owner of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of December, 19 62

My commission expires May 20, 1964

Milton J. Volin
Notary Public.

DRILLER'S LOG

COMPANY:
CONTRACTOR:
FAH:
LOCATION:
COMMENCED:
COMPLETED:

Inger Oil Company
LOBEN DRILLING, INC.
GILES #1
C NW NE Sec. 34-25S-16W
EDWARDS COUNTY, KANSAS
6-21-62
7-4-62

0 230
230 275
275 330
330 407
407 1065
1065 1100
1100 1910
1910 2410
2410 2535
2535 2625
2625 3125
3125 3400
3400 3495
3495 4374
4374 4384
4384 4409
4409 4429
4429 4449
4449 4490
4490 4620

Sand
Shale
Sand
Shale
Shale & Redbed
Anhydrite
Shale & Shells
Lime
Lime & Shale
Lime
Lime & Shale
Lime
Lime & Shale
Lime
Conglomerate
Conglomerate & Lime
Sand & Shale
Lime, Shale & Sand
Lime
Rotary Total Depth - Set 5 1/2" casing

RECEIVED
STATE CORPORATION COMMISSION

AUG 7 1962

CONSERVATION DIVISION
Wichita, Kansas

Set 8 5/8" surface casing @ 407' cemented with 265 sacks of Common NA5 by HOMO.

I, Byron Johnson, do hereby certify that the above and foregoing is a true and correct copy of the log of the Giles #1 located C NW NE of Section 34, Township 25 South, Range 16 West of Edwards County, Kansas, as reflected by the files of Loben Drilling, Inc.

Byron Johnson
Byron Johnson

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 10th day of July, 1962.

Ulanda Nichols
Ulanda Nichols

My Commission Expires:
April 1, 1963

