


15-047-20673-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202



Locate well correctly on above Section Flat

Edwards County. Sec. 34 Twp. 25S Rge. 16W E/W  
Location as "NE/CNW/SW" or footage from lines  
SE SW SE

Lease Owner DuPont Oil Company  
Lease Name WILSON Well No. 2  
Office Address 660 Edgewater Road, Wichita, KS 67230  
Character of Well (Completed as Oil, Gas or Dry Hole)

Dry hole  
Date Well completed May 19 19 80  
Application for plugging filed (Verbally) May 19 19 80  
Application for plugging approved (Verbally) May 19 19 80  
Plugging commenced May 19 19 80  
Plugging completed May 19 19 80

Reason for abandonment of well or producing formation  
No commercial quantity of oil or gas encountered  
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Owens  
Producing formation Depth to top Bottom Total Depth of Well 4452'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.


T.D. 4452'.  
Set 1st plug at 450' with 50 sacks,  
40' solid bridge,  
rathole with 10 sacks,  
water well with 2 sacks.

Plug was down at 11:30 p.m., 5-19-80.

6-5-80

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.



STATE OF Kansas COUNTY OF Sedgwick  
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge  
801 Union Center, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of June, 19 80



Sherrie L. Brooks  
Sherrie L. Brooks Notary Public.

My commission expires

CONTRACTOR'S WELL LOG

OPERATOR:	DuPont Oil Company
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	WILSON #2
LOCATION:	SE SW SE, Section 34-25S-16W, Edwards County, Kansas
SPUD DATE:	5-9-80
COMPLETION DATE:	5-19-80

0	495	Sand & Red Bed
495	1313	Lime & Shale
1313	2005	Red Bed & Shale
2005	4452	Lime & Shale
	4452	Rotary Total Depth

Spud hole at 7:30 a.m., 5-9-80. Drilled 495' of 12-1/4" hole. Ran 11 joints of 8-5/8" 20# casing. (Tally 444') Set at 454'. Cemented with 425 sacks of blended cement. Plug was down at 2:30 p.m., 5-9-80. Cement did circ.

T.D. 4452'. Set 1st plug at 450' with 50 sacks, 40' solid bridge, rathole with 10 sacks, water well with 2 sacks. Job was complete at 11:30 p.m., 5-19-80.

SAMPLE TOPS:

Anhydrite 1079'(+1006)  
B/Anhydrite 1092'(+ 993)

6-5-80

RECEIVED  
JUN - 5 1980  
COUNTY CLERK  
SEDGWICK COUNTY, KANSAS

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK )

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the WILSON #2, SE SW SE, Section 34-25S-16W, Edwards County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge  
Jack L. Partridge, Asst. Sec.-Treas.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 2nd day of June, 1980.

Sherrie L. Brooks  
Sherrie L. Brooks

