


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Edwards County, Sec. 34 Twp. 25 Rge. 16 (E) (W)

Location as "NE/CNW%SW%" or footage from lines NW NW SE  
Lease Owner Inger Oil Company  
Lease Name Wilson Well No. 1  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 8-22-63 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 8-24-63 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation Depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4525 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	380'	None
				5-1/2"	4525'	3454'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 4380', sanded to 4340' and dumped 5 sacks of cement @ 4340' with dump bailer. Pulled 5 1/2" casing, bailed fluid from 80' to 300', set rock bridge to 290' and ran 20 sacks of cement @ 290'. Mudded to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 29 1963

8-29-63  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING COMPLETE.

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.  
Noel J. Knight (employee of owner) or ~~owner~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of August, 1963

Milton J. Volin

Notary Public.

My commission expires May 20, 1964

15-047-10142-0000


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- JOHNSTON & LARIMER, INC.  
Farm- Wilson No. 1

SEC. 34 T. 25 R. 16W  
NW NW SE

Total Depth. 4525'  
Comm. 12-2-58 Comp. 12-16-58  
Shot or Treated.  
Contractor. Lauck Drilg. Co.  
Issued. 7-10-59

County Edwards  
KANSAS



CASING:

8 5/8" 330' cem w/225 sx.  
5 1/2" 4525' cem w/100 sx.

Elevation. 2065' DF

Production. 5,000,000 CFG

Figures Indicate Bottom of Formations.

sand & clay	20
sand & gravel	235
shale	320
sand	365
red bed	380
red bed	1030
Anhydrite	1050
shale & shells	2013
lime & shale	3645
lime	3748
Heebner	3754
lime & shale	3895
lime	4250
lime & shale	4320
lime	4380
lime, shale, chert & sand	4403
chert & shale	4443
shale	4460
sand	4470
chert & shale	4505
shale	4509
Viola	4525 RID
Total Depth	

TOPS: SCOUT

Heebner	3748
Toronto	3767
Douglas	3787
Brown Lime	3892
Lansing	3908
Base Kansas City	4201
Cherokee Sand	4358
Conglomerate	4391
Mississippi	4415
Kinderhook Sand	4456
Viola	4510

**RECEIVED**  
STATE CORPORATION COMMISSION

FEB 6 1961

CONSERVATION DIVISION  
Wichita, Kansas

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
505 East Murdock, Wichita, Kansas

Company: JOHNSTON & LARIMER, INC.  
Farm: Wilson No. 1

SEC. 34 T. 25 N. 16W  
NW NW SE

Total Depth: 4525'  
Comm. 12-2-58 Comp. 12-16-58  
Shot or Treated.  
Contractor: Lauck Drig. Co.  
Traced: 7-18-59

County: Edwards  
KANSAS



CASING:

8 5/8" 380' cen w/225 sx.  
5 1/2" 4525' cen w/100 sx.

Elevation: 2065' DF

Production: 5,000,000 CPO

Figures Indicate Bottom of Formations.

sand & clay	20
sand & gravel	235
shale	320
sand	365
red bed	300
red bed	1030
Anhydrite	1050
shale & shells	2013
lime & shale	3645
lime	3748
Heebner	3754
lime & shale	3095
lime	4250
lime & shale	4320
lime	4380
lime, shale, chert & sand	4403
chert & shale	4443
shale	4460
sand	4470
chert & shale	4505
shale	4509
Viola	4525 LTD
Total Depth	

TOPS: SCOUT

Heebner	3748
Toronto	3767
Douglas	3787
Brown Line	3892
Lansing	3908
Base Kansas City	4201
Charokee Sand	4350
Conglomerate	4391
Mississippi	4415
Kinderhook Sand	4456
Viola	4510

RECEIVED  
STATE CORPORATION COMMISSION

AUG 22 1960