

TATE OF KANSAS
TATE CORPORATION COMMISSION
30 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-02-3-117

API NUMBER 15-047-20052-0000

LEASE NAME Julian "A"

WELL NUMBER 3

660 Ft. from S Section Line

1650 Ft. from ~~X~~ Section Line

SEC. 8¹⁵ TWP. 25 RGE. 16W (E) or (W)

COUNTY Edwards

Date Well Completed _____

Plugging Commenced 7-26-00

Plugging Completed 7-28-00

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR D.R. Lauck Oil Company, Inc.

ADDRESS 110 N. Main Ellinwood, Kansas 67526

PHONE (316) 564-2013 OPERATORS LICENSE NO. 5427

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom T.D. 4451'

Show depth and thickness of all water, oil and gas formations.

RECEIVED
STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

8-9-00
AUG 9 2000

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	294'	None
				5-1/2"	4451'	2217'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each section. Plugged off bottom with sand to 4250' and 5 sks. cement. Shot pipe @2432 and 2217', pulled up to 1050', pumped 10 sks. gel, 50 sks. cement, 2 sks. gel, pulled to 325', pumped 50 sks. cement, pulled to 40' and topped off with 10 sks. cement, 60/40 pos. 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: D.R. Lauck Oil Company, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 8th day of August, 2000.

[Signature]
Notary Public

My Commission Expires:

IRENE HERZBERG
State of Kansas
My Appt. Exp. Aug. 24, 2001

Revised 05-