

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
206 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-047-20381-0000

LEASE NAME Wilson

WELL NUMBER 2-29

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 29 TWP. 25 RGE. 18W (E) or (W)

COUNTY Edwards

Date Well Completed         

Plugging Commenced 12/14/88

Plugging Completed 12/16/88

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Murfin Drilling company

ADDRESS 250 N. Water #300  
Wichita, KS 67202

PHONE# (316) 267-3241 OPERATORS LICENSE NO. 6033

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on          (date)

by          (KCC District Agent's Name).

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 4723

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	496	none
				4 1/2	3248	1774

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet each set.

Plugged bottom with sand to 2560', dumped 4 sacks cement, shot @1822', 1774',  
plugged surface with 400# hulls, 10 gel, 50 sacks cement, 10 gel, 100# hulls,  
120 sacks 60/40 poz, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of  
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,  
statements, and matters herein contained and the log of the above-described well as filed that  
the same are true and correct, so help me God.

STATE CORPORATION COMMISSION

(Signature) R. Darrell Kelso


(Address) P.O. Box 347 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 19th day of December, 1988

CONSERVATION DIVISION  
Wichita, Kansas

My Commission Expires:         

J. J. Hoover  
Notary Public



# WELL LOG

15-047-20381-0000

COMPANY Murfin Drilling Company

SEC. 29 T. 25S R. 18W  
LOC. C NW SE

FARM WILSON NO. 2-29

RIG. NO. 19


TOTAL DEPTH 4715' PBSD 3550'

COUNTY Edwards  
KANSAS

COMM. August 1, 1978

COMP. August 14, 1978

CONTRACTOR Murfin Drilling Company



**CASINO**

20 TD  
15 0 -5/8" @ 496' w/350 sx.  
12 4  
13 5  
4 1/2" @ 3240' w/350 sx.

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

160'	Sand	
670'	Shale	
700'	Lime	
1067'	Shale - Red Beds	
1262'	Shale	
1280'	Anhydrite	
2270'	Shale & Lime	
2435'	Lime & Shale	
2920'	Shale & Lime	
3210'	Lime	
3302'	Lime & Shale	
3571'	Shale & Lime	
4423'	Lime & Shale	
4647'	Lime	
4715'	Lime & Chert	RTD

**RECEIVED**  
STATE CORPORATION COMMISSION

NOV 7 1988  
11-7-88  
CONSERVATION DIVISION  
Wichita, Kansas