

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-055-20317-0000

LEASE NAME TATE

WELL NUMBER 1

SPOT LOCATION Center

SEC. 35 TWP. 24 RGE. 31 ~~W~~ or (W)

COUNTY Finney

Date Well Completed 8/5/78

Plugging Commenced 10/12/84

Plugging Completed 10/12/84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Energy Exploration & Production, Inc.

ADDRESS 5501 Foxridge Drive, Mission, Kansas 66202

PHONE # (913) 722-5955 OPERATORS LICENSE NO. 5639

Character of Well Gas  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing formation Krider Depth to top 2,670 bottom 2,680 T.D. 2,750

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Krider</u>	<u>Gas</u>	<u>2,670</u>	<u>2,680</u>	<u>8-5/8"</u>	<u>610</u>	<u>None</u>
				<u>4-1/2"</u>	<u>2,750</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Pumped 50 sacks on bottom; 20 sacks at 1,330 feet; 100 sacks at 700 feet; pumped 85 sacks between surface pipe and casing; cut off casing and surface pipe 4 feet below ground level; filled 4-1/2" casing with cement from about 25 feet to top of casing.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Post & Mastin License No. 8438  
Address Box 297, Garden City, Kansas 67846

11-2-84  
RECEIVED

STATE OF Kansas COUNTY OF Johnson, ss.

STATE CORPORATION COMMISSION

Clay E. Hedrick, Jr., employee of operator (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God. NOV 02 1984  
CONSERVATION DIVISION  
Wichita, Kansas

(Signature) Clay E. Hedrick, Jr.  
(Address) Box 366, Newton, Kansas 67114

SUBSCRIBED AND SWORN TO before me this 31st day of October, 1984

John L. Dullman  
Notary Public

My Commission expires: 7-23-86