

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-055-00833-0000

API NUMBER \_\_\_\_\_

LEASE NAME Webster A-1

WELL NUMBER 1

SPOT LOCATION CNW/4

SEC. 31 TWP 24 RGE. 31 (E) or (W)

COUNTY Finney

Date Well Completed 7-29-62

Plugging Commenced 8-10-84

Plugging Completed 8-13-84

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR K N Energy, Inc.

ADDRESS P.O. Box 15265; Lakewood, Co. 80215

PHONE # (310) 355-7122 OPERATORS LICENSE NO. 5270

Character of Well Gas  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing formation Upper Krider Depth to top 2518 bottom 2528 T.D. 2610

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Winfield	Gas	2571	81	8 5/8"	298	3'
Lower Krider	Gas	2538	48	4 1/2"	2607	598'
Upper Krider	Gas	2518	28			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set. Pumped 1 sk. hulls and 25 sx cement to 2460'. Shot pipe at 596' and pumped 20 sk. cement 570' to 500'. Pumped 25 sx cement, 340' to 240'; put bridge and 10 sx cement 40' to 0'. Cut off 8 5/8", 3' below GI and welded plate on same.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497

Address Box F; Sublette, Kansas 67877

9-18-84

RECEIVED

STATE OF Kansas COUNTY OF Haskell, ss. STATE CORPORATION COMMISSION

Steven Steele (employee of operator) or  
(operator) of above-described well, being first duly sworn on oath, says: That  
I have knowledge of the facts, statements, and matters herein contained and  
the log of the above-described well as filed that the same are true and  
correct, so help me God.

SEP 18 1984

CONSERVATION DIVISION  
Wichita, Kansas

(Signature) Steven Steele

Route 2, Box 16

(Address) Lakin, Kansas 67860



SUBSCRIBED AND SWORN TO before me this 17 day of Sept., 1984

Ann Dyer  
Notary Public

My Commission expires: 9-1-86