

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-055-20,269-0000

LEASE NAME Fuller

WELL NUMBER No.1

2640 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 3 TWP. 24S RGE. 31 (E) or (W)

COUNTY Finney

Date Well Completed June 25, 1977

Plugging Commenced Nov 17, 1992

Plugging Completed Nov 18, 1992

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR American Warrior, Inc.

ADDRESS P.O. Box 399 Garden City, KS. 67846

PHONE# (316) 275-2963 OPERATORS LICENSE NO. 4058

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 16, 1992 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? YES If not, Is well log attached? -

Producing Formation Chase Perfs Depth to Top 2677 Bottom 2682 T.D. 2740

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Chase	Gas & Water			7	348	NONE
				4 1/2	2694	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Ran 2 3/8" tubing to 2673', pump 1 sack hulls and 35 sacks 60 - 40 Poz mix, 3% gell, 2% CC.

Pull tubing to 2000', pump 140 sacks cement same as above. Circulate cement to G.I. Lay down rest of tubing. Top off casing with 28 sacks cement. pump 197 sacks cement down backside.

Shut down with 150 lbs. on annulus. plugged at 6:00 p.m. 11-17-92

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Murfin Well Service License No. 6033

Address 250 N. Water #300, Wichita, KS. 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: American Warrior, Inc. 12-8-92

STATE OF Kansas COUNTY OF Finney, ss.

Michael J. Wreath (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Michael J. Wreath DIVISION

(Address) P.O. Box 399, Garden City, KS. 67846

NOTARY PUBLIC  
DONNATE G. THODE  
Finney County  
STATE OF KANSAS  
My Appt. Exp. 11/9/94

CREATED AND SWORN TO before me this 4th day of December, 19 92

Donnate G. Thode  
Notary Public

My Commission Expires: Nov. 9, 1994

WELL NO. 1 LEASE FULLER TICKET NO. 15-05520269-0000  
 CUSTOMER AMERICAN WARRIOR PAGE NO. 10 25105915  
 JOB TYPE PTA DATE 11-17-92

TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
			T	C	TUBING	CASING	
1000							Time Collected
1300							Time Ready
1250							Time on hole
1430							Hookup To Tub At 2673 FT
1435	12.5	5			177.7		Start water ahead
1437		8.4					Start Mixing Cement 35 SK cement + 1 SK Halls
1441		8.2					Start Dip Subst Pumpst Lines
1445							Shut Down Break Loss
							Pig Pick Tub To 2100 FT
1515							Hookup To Tub 2000 FT
1520	3 BH						Start Mixing Cement
1531		34 BH					Finish Mix Cement w 140 SK
1530							Circulate Cement To Ground Level
1532							Shut Down + Break Loss
							Pig Trip Tub OUT OF HOLE
							3 <sup>rd</sup> Stop OFF casing w/ cement 28 SK
1650							Start Mixing Cement
1655		7					Shut Down Circ Cement To Ground Level
							Hookup BS 197 SK
1715							50 Start Pump Cement
1730		117 BH					150 Shut Down Shut Valve w 150 PSI on Cas

Thanks For Getting  
 Hollister  
 Sevens  
 Doney  
 Cull

CUSTOMER  
 CUSTOMER