

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Hamilton County. Sec. 21 Twp. 24S Rge. 41(W)

Location as "NE/CNW/SW" or footage from lines Ctr SW SW 4E

Lease Owner Texaco Inc.

Lease Name K. A. Scott Well No. 1

Office Address 614 Bitting Bldg., Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Gas (SI)

Date well completed 9-18-1963

Application for plugging filed 10-4-1966

Application for plugging approved 10-4-1966


Plugging commenced 10-5-1966

Plugging completed 10-5-1966

Reason for abandonment of well or producing formation Uneconomical to produce, well logged off with saltwater.

If a producing well is abandoned, date of last production (Test) June 1964

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well E. Eves, Sublette, Kansas

Producing formation Winfield Depth to top 2324 Bottom 2351 Total Depth of Well 2351 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Winfield	Gas	2324	2351	7"	409	None
				4 1/2"	2324	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

No casing recovered. Hole plugged as follows: 2351-2200 w/15 sxs cmt, 2200-459 w/hvy drlg mud, 459-359 w/10 sxs cmt, 359-50 w/hvy drlg mud, 50-0 w/5 sxs cmt. Comp 3 PM 10-5-66.

STATE CORPORATION COMMISSION
12-15-66
DEC 15 1966

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargents Casing Pulling Service, 121 West 9th,
Address Liberal, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
M. R. Wilson (employee of owner) or ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. R. Wilson

614 Bitting Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of December, 19 66

Dorothy Sue Jones
Notary Public.

My commission expires 10-13-69

15-075-10121-0000

CONTRACTOR'S WELL LOG

CONTRACTOR:
OWNER:
WELL:
LOCATION:
COMMENCED:
COMPLETED:

CHEMICAL & TECHNICAL SERVICES, INC.
TEXACO INC.
SCOTT UNIT #1
SW SE SEC. 21-24S-41W
HAMILTON CO., KANSAS
9/3/63
9/7/63

0	115	SAND
115	409	SHALE
409	545	SHALE & SHELLS
545	930	SAND, SHALE & SHELLS
930	1823	SHALE & RED BED
1823	1835	ANHYDRITE
1835	2335	SHALE & LIME
2335		ROTARY TOTAL DEPTH

RECEIVED
STATE CORPORATION COMMISSION
10-4-66
OCT 4 1966

SET 7" SURFACE CASING @ 409' W/250 SACKS CEMENT
SET 4-1/2" PRODUCTION CASING @ 2320' W/140 SACKS CEMENT

WE HEREBY CERTIFY THIS TO BE A CORRECT AND ACCURATE LOG OF THE ABOVE DESCRIBED WELL,
AS SHOWN ON THE DAILY DRILLING REPORTS.

CHEMICAL & TECHNICAL SERVICES, INC.

BY: D. J. McCarthy
ASST. TREASURER

SUBSCRIBED AND SWORN TO BEFORE THIS 16th DAY OF SEPTEMBER, 1963.

Clara Lusk
NOTARY PUBLIC

My Commission Expires January 23, 1964