

WELL PLUGGING RECORD

Finney County, Sec. 17 Twp. 26S Rge. 33W (W)

Location as "NE/CNW/SW" or footage from lines NW SE

Lease Owner: Mallonee-Mahoney, Inc.

Lease Name: Sinn #1 Well No.

Office Address: P.O. Box 1257, Liberal, Kansas 67901

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 6/4/ 19 70

Plugging completed 6/5/ 19 70

Reason for abandonment of well or producing formation


If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced?

STATE OF KANSAS STATE CORPORATION COMMISSION

Give All Information Completely Make Required Affidavit Mailer Deliver Report to: Conservation Division State Corporation Commission 211 No. Bandway Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mix 20 sks. cement and 1 sk. hulls to plug off perms. Stop plug at 4,500'. Pump 40 sks. cement at 800' to 700'. Put 15 sks. cement at 45' to 0'.

RECEIVED STATE CORPORATION COMMISSION JUN 22 1970 CONSERVATION DIVISION Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor: Sargents Casing Pulling Service Address: P.O. Drawer 506, Liberal, Kansas 67901

STATE OF KANSAS, COUNTY OF SEWARD, ss. Robert Sargent

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert Sargent P.O. Box 506, Liberal, Kansas 67901 (Address)

Subscribed and Sworn to before me this 15th day of June, 19 70



Frances Anderson Notary Public. FRANCES ANDERSON, NOTARY PUBLIC MY COMMISSION EXPIRES MAY 7, 1972

DRILLING LOG

LEASE OWNER Mallonee-Coppinger Operations, Inc.
ADDRESS 925 Sutton Place, Wichita, Kansas 67202

LEASE Sinn #1
DESCRIPTION C NW SE Section 17-26S-33W, Finney County, Kansas

12-9-67 Spud 1:30 p.m.

12-10-67 Ran 20 jts 8 5/8" 23# Casing, 1 jt 24# Casing @ 849' KB
 Cement with 400 Pozmix, 4% added Gel, 2% CC, tailed with
 150 sx Common, 3% CC. Plug down at 9:00 a.m. Cement Circulated.

12-26-67 Ran 166 jts 4 1/2" 10.5# Casing - 103 new, 63 used. Cemented
 with 200 sx 50-50 Pozmix, 12 1/2# Gilsonite per sack. Plug down
 at 8:00 p.m.

FORMATION AND DEPTH


| | |
|----------------------------|-------------|
| Sand and Shale | 0 - 640 |
| Shale, Anhydrite | 640 - 850 |
| Red Bed, Shale, Anhydrite | 850 - 1030 |
| Red Bed, Shale | 1030 - 1393 |
| Sand | 1393 - 1585 |
| Red Bed, Shale | 1585 - 1680 |
| Red Bed, Shale & Anhydrite | 1680 - 1980 |
| Shale, Anhydrite | 1980 - 2590 |
| Shale, Lime | 2590 - 2980 |
| Lime, Shale | 2980 - 3468 |
| Shale, Lime | 3468 - 3918 |
| Lime, Shale | 3918 - 5055 |
| Lime | 5055 - 5066 |
| Lime & Shale | 5066 - 5166 |
| Lime | 5166 - 5260 |
| TD | 5260 |

THIS IS A TRUE AND EXACT COPY OF THE FORMATIONS TAKEN FROM THE DAILY DRILLING REPORTS.

Executed this 28th Day of December, 1967:

William F. Dean
 William F. Dean
 William F. Dean

IN WITNESS WHEREOF, I have hereunto set my hand and affixed my official seal the day and year above written.



Jelena Dorsett
 Notary Public

MY COMMISSION EXPIRES: January 31, 1971