

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-055-20.565-0000

LEASE NAME Stone Farms Unit

WELL NUMBER #1

SPOT LOCATION C NW SW

SEC. 17 TWP. 26 RGE. 33 (X) or (W)

COUNTY Finney

Date Well Completed 09/05/84

Plugging Commenced 09/06/84

Plugging Completed 09/07/84

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Pan Western Energy Corporation

ADDRESS 324 S. Main, Suite 711 Tulsa, OK 74103

PHONE #(918) 582-4957 OPERATORS LICENSE NO. 7771

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Paul Luthi State Plugger

Is ACO-1 filed? Yes If not, is well log attached? Yes

Producing formation _____ Depth to top _____ bottom _____ T.D. 5258'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface Casing	0'	1652	8 5/8"	yes	no

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

1st Plug @ 1820' W/70 sx
2nd Plug @ 1110' W/40 sx
3rd Plug @ 630' W/30 sx (All Cement 60/40 poz, 2% gel, 3% cc.)
Top Plug @ 40' W/10 sx
15 sx in Rathole

(If additional description is necessary, use BACK of this form.)

10-4-84

Name of Plugging Contractor Halliburton License No. 5287
Address 202 West First Street, Wichita, KS 67202

RECEIVED
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Sedgwick, ss. OCT 04 1984

James C. Remsberg, Slawson Drilling Company, Inc. (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says that I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so

REBECCA WOLD
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. 10-20-85

(Signature) James C. Remsberg
(Address) James C. Remsberg, President
200 Douglas Bldg. Wichita, KS

SUBSCRIBED AND SWORN TO before me this 27 day of Sept, 1984

Rebecca Wold
Notary Public

My Commission expires: 10-20-85

DRILLERS LOG

OPERATOR: Pan Western Energy Corporation
324 S. Main, Suite 711
Tulsa, KS 74103

LEASE NAME: Stone Farms Unit #1
C NW SW Sec. 17-26-33W
Finney County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.
200 Douglas Bldg.
Wichita, KS 67202

RTD: 5258'

SURFACE CASING: 8 5/8" set at 1652' with 750 sx cement

0' to 900'	12 1/4" Surface Hole
900' to 1672'	Red Bed
1672' to 2350'	Red Bed & Shale
2350' to 4510'	Lime & Shale
4510' to 4625'	K.C. Marmaton
4625' to 4895'	Lime & Shale
4895' to 5115'	Morrow Sand
5115' to 5195'	St. Louis Sand
5195' to 5258'	Mississippi
5258' RTD	


STATE OF KANSAS


COUNTY OF SEDGWICK

I, James C. Remsberg, of the Slawson Drilling Company, Inc. hereby state the above is an accurate copy of the drillers log for the Stone Farms Unit #1 for Pan Western Energy Corporation.


James C. Remsberg, President

Subscribed and sworn to me this
21st day of September, 1984


Rebecca Wold, Notary



My Commission expires: 10-20-85

10-4-84

RECEIVED
NOTARY COMMISSION

OCT 04 1984

CONSERVATION DIVISION
Wichita, Kansas