

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15 055-20684-000

LEASE NAME Schauf

WELL NUMBER 1-A - 36

SPOT LOCATION 50'S SE NW

SEC. 36 TWP. 26 RGE. 32 (E) or (W)

COUNTY Finney

Date Well Completed 3-5-87

Plugging Commenced 12-787

Plugging Completed 12-10-87

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Global Natural Resources

ADDRESS P.O. Box 4682, Houston, TX. 77210

PHONE # (713) 880-5464 OPERATORS LICENSE NO. 4238

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing formation St. Louis Lime Depth to top 5089 bottom 5107 T.D. 5280

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface				8 5/8"	1920	0'
Production				5 1/2"	5280	1800'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Pump 2 sks. hulls & 20sks. cement to 4950'  
Pressured to 750 lbs. - Pumped 40 sks. cement 1800' to 1680'  
Mud to 1680' to 800' - Pumped 40sks. cement 800' to 680'  
Put bridge and 10 sks. cement 40' to 0'  
Cut off 8 5/8", 3' below ground level and cap

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497  
Address Box F, Sublette, Ks. 67877

RECEIVED  
12-16-87  
DEC 16 1987  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS COUNTY OF HASKELL, ss.

Edgar J. Eves (operator) or  
(operator) of above-described well, being first duly sworn on oath, says: That  
I have knowledge of the facts, statements, and matters herein contained and  
the log of the above-described well as filed that the same are true and  
correct, so help me God.



(Signature) Edgar J. Eves  
(Address) Box F, Sublette, Ks. 67877

SUBSCRIBED AND SWORN TO before me this 12 day of Dec., 19 87

Sondra L. Eves  
Notary Public

My Commission expires: 12-6-88

15 - 055-20684-0000



# ACOUSTIC CEMENT BOND LOG

BOND LOG

COMP. GLOBAL NATURAL RESOURCES WELL SCHAUF NO. 1-36 FIELD CASSIDY EAST PROSPECT COUNTY FINNEY ST. KS	COMPANY GLOBAL NATURAL RESOURCES						
	WELL SCHAUF NO. 1-36						
	FIELD CASSIDY EAST PROSPECT						
	COUNTY FINNEY	STATE KS					
	API NO. 05520687 <i>684-0000</i>	OTHER SERVICES					
LOCATION SH/NW 3250 FSL 3300 FEL							
SEC. 36	THP. 26 S	RGE. 32 W					
PERMANENT DATUM	GROUND LEVEL	ELEV. 2841					
LOG MEASURED FROM	KELLY BUSHING 13 FT. ABOVE PERM. DATUM	ELEV. : K.B. 2854					
DRILLING MEASURED FROM	KELLY BUSHING	D.F. ---- G.L. 2841					
DATE & TIME LOGGED	02-04-87 / 3:30 PM	TYPE OF FLUID IN HOLE					
RUN NO.	ONE	DENSITY OF FLUID					
DEPTH - DRILLER	5280	FLUID LEVEL					
DEPTH - WELEX	5237	CEMENT TOP EST. - LOGGED					
BTM. LOGGED INTERVAL	5228	EQUIPMENT : LOCATION					
TOP LOGGED INTERVAL	1920	RECORDED BY					
MAX TEMP. DEGREE		WITNESSED BY					
CEMENTING DATA	SURFACE STRING	PROTECTION STRING					
DATE/TIME CEMENTED		STATE CORPORATION COMMISSION					
PRIMARY/SQUEEZE							
EXPECTED COMP. STRENGTH		NOV 23 1987					
CEMENT VOLUME	SEE REMARKS	CONSERVATION DIVISION					
CEMENT TYPE/WEIGHT		Wichita, Kansas					
FORMULATION							
MUD TYPE/MUD WEIGHT							
RUN NO.	BOREHOLE RECORD			CASING AND TUBING RECORD			
	BIT	FROM	TO	SIZE	WGT.	FROM	TO
				5.5	15.5	SURF	T.D.