



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JAN 29 1964

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Copeland of Western Petroleum Co. Inc has this date requested permission to plug the following described well:

Mr. Copeland guarantees payment of the plugging fee.

Operator's full Name: Western Petroleum Co., Inc.

Complete Address: 925 Patton Road, Great Bend, Kansas

Lease Name: Hart Well No. # 2

Location: C N/2 SW Sec. 22 Twp. 25 Rge. 15 (E) (W) W

County Stafford Total Depth 4445 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Copeland was instructed to plug the well as follows:

298' of 8 5/8" surface pipe, cemented with 320 sacks.

Fill hole with mud to 275', 1st cementing plug, bridge with

hulls, and cement with 25 sacks. Fill hole with mud to 40',

2nd cementing plug, bridge with hulls, and cement with 10 sacks

to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent