

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

APR 26 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts.
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Elmo Finch of Pipe Pullers Inc. has this

date requested permission to plug the following described well:

Mr. Finch guarantees payment of the plugging fee.

Operator's full Name: Isern - Wells Drilling Co.

Complete Address: Box 486, Ellinwood, Kansas

Lease Name: Haynes Well No. # 1

Location: NW NW SE Sec. 22 Twp. 25 Rge. 15 (E) (W) W

County Stafford Total Depth 4578 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Finch was instructed to plug the well as follows:

360' of 8 5/8" surface pipe cemented with 350 sacks.

4578' of 5 1/2" long string cemented with 150 sacks. Plugged

Back to 4320'. Perforated 4251' to 60'. Sanded to 4220'.

rock bridge and 5 sacks cement. Plug set a 225', 10'

rock bridge cement with 20 sacks. Fill hole to 40', 19'

Rock Bridge cement with 10 sacks to base cellar.

Very truly yours,

Archie Elving
 Conservation Division Agent