

State of Kansas



15-185-30185-0000
FORM - CP-2
Rev. 6-26-62

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 22 1965
10-22-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Max Lattimer of Raymond Oil Company, Inc. has this date requested permission to plug the following described well:

Mr. Lattimer guarantees payment of the plugging fee.

Operator's full Name: Raymond Oil Company, Inc.

Complete Address: 410 Fourth National Bank Bldg., Wichita, Ks.

Lease Name: Wilson Well No. # 1

Location: App. C SW SE . Sec. 24 Twp. 25 Rge. 15 (E) (W) W

County Stafford Total Depth 1859' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lattimer was instructed to plug the well as follows:

274' of 8 5/8" surface pipe, cement circulated with 275 sacks.
Fill hole with drilling mud to 260', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling mud
to 40', 2nd cementing plug, bridge with hulls, and cement with 10
sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,
Archie Elving