



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 12 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. DeLaney of Leben Drlg. Inc. has this
date requested permission to plug the following described well:

Mr. DeLaney guarantees payment of the plugging fee.

Operator's full Name: Leben etal

Complete Address: 200 W Douglas Wichita, Ks

Lease Name: Cotton Well No. 2

Location: C NE/SW Sec. 8 Twp. 25s Rge. 15 (E)(W) W

County: Stafford Total Depth 3985 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. DeLaney was instructed to plug the well as follows:

679 ft 8 5/8 surface pipe cemented with 400 sacks. Pump

40 sacks cement to 600 ft. 2nd plug at 250 ft with 20 sacks

cement. Mud to 40 ft, plug, 1/2 sack hulls, 10 sacks cement

to surface. 2 sacks cement in rat hole.

Pumped by Sun Cementing Co. Great Bend, Ks

Very truly yours,

L. Russell Bihurst
Conservation Division Agent