



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAR 20 1964

3-20-64

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Copeland of Western Petroleum Co., Inc has this  
date requested permission to plug the following described well:

Mr. Copeland guarantees payment of the plugging fee.

Operator's full Name: Nadel and Gussman & Western Petroleum, Co.

Complete Address: 1714 1st National Bldg., Tulsa, Oklahoma

Lease Name: Stanbaugh "A" Well No. # 1

Location: C NW NW Sec. 25 Twp. 25 Rge. 15 (E) (W) W

County Stafford Total Depth 4399 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Copeland was instructed to plug the well as follows:

264' of 8 5/8" surface pipe, cement circulated. Fill hole  
with drilling mud to 250', 1st cementing plug, bridge with  
hulls, and cement with 25 sacks. Fill hole with drilling  
mud to 40', 2nd cementing plug, bridge with hulls, and cem-  
ent with 10 sacks to base cellar. Bridge and cement rat hole  
with 2 sacks.

Very truly yours,

Archie E. Elving  
Conservation Division Agent