

State of Kansas

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JUL 15 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Deacon of Forbes Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Deacon guarantees payment of the plugging fee.

Operator's full Name: Petrop International Oil Co.

Complete Address: 700 Petroleum Bldg., Tulsa, Oklahoma

Lease Name: Lamb Well No. # 1

Location: C NW SE Sec. 30 Twp. 25 Rge. 15 (E) (W) W

County Stafford Total Depth 4380 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Deacon was instructed to plug the well as follows:

400' of 8 5/8" surface pipe, cement circulated with 250
sacks. 4378' of 4 1/2" long string, cemented with 100 sacks.
Top perforation 4314'. Sand to 4300', cement with 3 sacks.
Fill hole with mud to 240', 10' rock bridge, cement with
20 sacks. Fill hole with mud to 40', 10' rock bridge,
cement with 10 sacks to base cellar.

Very truly yours,

Archie Elving
 Conservation Division Agent