

15-159-06428-000

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
NOV 29 1966
11-29-66
CONSERVATION DIVISION
WICHITA, KANSAS

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

November 12, 1966

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Sam Bradlev of Pine Pullers, Inc. has this
date requested permission to plug the following described well:

Mr. Bradlev guarantees payment of the plugging fee.

Operator's full Name: Meltzer Oil Company

Complete Address: Drawer "B", Great Bend, Kansas

Lease Name: Ploog Well No. 3

Location: E/2 E/2 SW Sec. 33 Twp. 18 Rge. 9 (E) (W) (N) (S)

County Rice Total Depth 3230' Oil Well Gas Well Input Well SWD Well D & A Lost Hole

Mr. Bradlev was instructed to plug the well as follows:

Fill hole with sand to 3200' and cement with 6 sacks.

Fill hole with mud to 185'. Set rock bridge from 185' to 175' and

cement hole with 35 sacks. Fill hole with mud to 30'. Set rock bridge

from 30' to 20' and cap hole with 15 sacks cement.

Very truly yours,

Conservation Division Agent