

State of Kansas



15-159-01483-0000

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

December 4, 1963

RECEIVED
STATE CORPORATION COMMISSION

DEC 18 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Donald Knight of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Great Bend Pipe & Supply Co., Inc.

Complete Address: Drawer "B", Great Bend, Kansas

Lease Name: Ploog Well No. 4

Location: SW $\frac{1}{4}$ Sec. 33 Twp. 18 Rge. 9 (E) (W) X

County Rice Total Depth 3210' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 3190' and cement with 6 sacks.

Fill hole with mud to 210'. Set rock bridge from 210' to

200' and cement hole with 40 sacks. Fill hole with mud to

35'. Set rock bridge from 35' to 30' and cap hole with

20 sacks cement.

Very truly yours,