

State of Kansas



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

April 12, 1969

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 APR 17 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 4-17-69

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Bob Herren of H-30 Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Herren guarantees payment of the plugging fee.

Operator's full Name: Mid-Continent-Marine Drilling, Inc.

Complete Address: P.O. Box 191, Mc Pherson, Kansas 67460

Lease Name: North Hilger Unit Well No. 1

2640' from South Line

Location: 75' from West Line Sec. 34 Twp. 25 Rge. 4 (K) (W) X

County: Reno Total Depth 4153' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Herren was instructed to plug the well as follows:

Fill hole with mud to 195'. Push plug and 1/4 sacks hulls to 195' and

cement hole with 35 sacks cement through drill pipe. Fill hole with mud

to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 13 sacks

cement. Bridge rathole and cement with 2 sacks.

Very truly yours,

  
 Conservation Division Agent