

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
WILLIAM G. GRAY
Carol J. Larson, Executive Secretary

Governor
Chairman
Commissioner
Commissioner

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

September 2, 1980

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 11 1980
CONSERVATION DIVISION
Wichita, Kansas
A-11-80

J. Lewis Bruck
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Rick Davis of H-30 Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Davis guarantees payment of the plugging fee.

Operator's full Name: Africa Explorations Inc., LTD

Complete Address: 1850 S. Boulder, Tulsa, Oklahoma

Lease Name: Harris Well No. 3

Location: 1200' E 1/2 330' EN 1/4 NW 1/4 Sec. 34 Twp. 25 Rge. 4 (E) (W) X

County: Reed Total Depth 4121 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Davis was instructed to plug the well as follows:

8 3/4 - 275 - 225 sacks Fill hole with mud. Pump 50 sacks
Cement through drill pipe at 350'. Fill hole with mud
to 40'. Push plug and 1/2 sack hulls to 40' and cap
hole with 10 sacks cement. Cement rat hole with
5 sacks cement.

Very truly yours,

Conservation Division Agent