

State of Kansas



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY O. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

January 2, 1965

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JAN 5 1965
1-5-65

CONSERVATION DIVISION
has this
Wichita, Kansas

Dear Sir:

Mr. Jack Gabbert of Gabbert-Jones, Inc.

date requested permission to plug the following described well:

Mr. Gabbert guarantees payment of the plugging fee.

Operator's full Name: Shawver-Armour, Inc.

Complete Address: 817 Central Bldg., Wichita, Kansas

Lease Name: Elling Well No. 1

Location: C NW SW Sec. 2 Twp. 25 Rge. 5 (E) (W) X

County Reno Total Depth 3905' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Gabbert was instructed to plug the well as follows:

Fill hole with mud to 230'. Push plug and $\frac{1}{2}$ sack hulls to
230' and cement hole with 20 sacks through drill pipe.

Fill hole with mud to 40'. Push plug and $\frac{1}{2}$ sack hulls to
40' and cap hole with 10 sacks cement.

Bridge rathole, and cement with 2 sacks.

Very truly yours,

William L. Mitchell
Conservation Division Agent