

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

*Plugging orders were issued
Nov 28, 1973.*

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
11-27-74
NOV 27 1974

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Robert W. Lange
Complete Address North Center St, Independence, Kans
Lease Name Catlett Miller Well No. #1
Location C. SE 1/4 Sec. 5 Twp. 24 Rge. (E) (W) 31
County Finney Total Depth 2715
Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Surgents Casing Pulling
Address Subersal, Kans. License No. 511

Operation Completed: Hour 5:00 PM Day 26th Month Nov Year 1974

The above well was plugged as follows:

*324 ft of 7 5/8" surface casing. 2715 ft
of 4 1/2" casing. Perforations 2678-2690.
2 sacks of Cotton seed Hulls + 15 sacks
Cement to seal off perforation. 20 sacks
Cement 700-550 ft. 20 sacks of cement
from 324 to 150 ft. 10 sacks cement
from 70 ft - 0. There was 1713 ft
of 4 1/2" casing salvaged.*

I hereby certify that the above well was plugged as herein stated.

Signed: Charles L. Thomas
Well Plugging Supervisor

INVOICED

DATE 12/2/74
INV. NO. 373-W