

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-097-20,617-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name F. X. O. Production Corp

Complete Address 200 W. Douglas Suite 300 Wichita, Kansas 67202

Lease Name Young "J" Well No. 1

Location 200' E of 1980' FWL Sec. 36 Twp. 27S Rge. 16W (East)(West)

County Kiowa Total Depth 4750'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated Well was completed but never produced.

Plugging Contractor Clarke Oilfield Service

Address 107 W. Fowler Medicine Lodge 67104 License No. 583

Operation Completed: Hour: 12:30 PM Day: 23 Month: March Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

There is 4749' of 4 1/2" production pipe cemented in. The perforations are from 4584' to 88'. 1st plug sandbed off bottom & 4 bbls of cement on top of sand bring top of cement to 4510'. Then pumped 15 bbls Gell + 6 bbls shells + 10 bbls Gell + 150 bbls of cement through head on surface casing. The hole was full of heavy mud before pumping last plug. The plugging was accomplished by allied cementing. They recovered 2703' of 4 1/2" production pipes.

Amount of Surface Casing: 409' of 8 5/8" cement circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthi
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

3-30-82

STATE RECEIVED

Signed: _____
Conservation Division Agent

MAR 30 1982
Conservation Division Agent
Wichita, Kansas

INVOICED

DATE 3-30-82

INV. NO. 9817-W