

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

6-26-62  
RECEIVED  
STATE CORPORATION COMMISSION

JUN 26 1962

CONSERVATION DIVISION  
Wichita, Kansas

TO:  
J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. 15-055-00070-0000 County: Finney

Location: NW SE Sec. 36 Twp. 26 Rge. (E) (W) 33

Name of Field: Kisner Gas Unit "C" Total Depth: 5500

I have this date completed supervision of plugging of:

Lease Name: Kisner Well No. I

Operator's Full Name: Pan American Petroleum Corporation

Complete Address: Box 507 Ulysses, Kansas

Plugging Contractor Knight Casing Pulling Co.

Address: Box 304 Chase, Kansas License No. 436

Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: Test well

Was any delay in plugging operations caused by Conservation Division Agent?

Yes  No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 3 PM Day 21 Month 6 Year 62

The above well was plugged as follows:

8 5/8" 1901' circulated w/1000 sax. cement.

4 1/2" 5500' cemented w/150 sax. Plug back to 5064. Top of perf. 4995, bottom 4997.

filled w/sand to 4980, dump 3 sax. cement. filled hole w/mud, pulled pipe to

650' set plug, pump 30 sax. cement, mud to 40' set 10' bridge, pump 10 sax. cement,

weld cap on surface pipe.

Signed: [Signature]  
Conservation Division Agent

Reviewed: [Signature]  
Field Supervisor

Remarks:

INVOICED  
DATE 6/27/62  
INV. NO. 5264-W