

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-155 20,816-0000 ✓ R200 Colorado Derby Bldg.
Wichita, KS 67202Operator's Full Name F & M Oil Company, Inc.Complete Address 422 Union Center, Wichita, Kansas 67202Lease Name Haines Well No. 1Location C SW SW Sec. 20 Twp. 25 Rge. 6 ~~(East)~~ (West)County Reno Total Depth 4060'Abandoned Oil Well ☐ Gas Well ☐ Input Well ☐ SWD Well ☐ D & A ☒

Other well as hereafter indicated _____

Plugging Contractor Mustang Drlg. & Expl., Inc. and Sun Oilwell Cementing, Inc.Address Box 1425, Great Bend, Kansas License No. _____Operation Completed: Hour: 10:15 PM Day: 3 Month: September Year: 19 81Plugging Operations attended by Agent? All ☐ Part ☐ None ☒The above well was plugged as follows: 8-5/8"-367'-275 sacks common 2% gel 3% CC

Hole circulated and filled with mud. 50 sacks cement pumped through
drill pipe at 375'. Hole filled with mud to 40'. Plug and 1/2 sack hulls
pushed to 40' and hole cemented to base of cellar with 10 sacks cement.
Rathole cemented with 10 sacks cement.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]

Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
SEP - 9 1981CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 10-29-81INV. NO. 8102-W

9-9-81

131.95