

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15- 614

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name City Service Oil Co.

Complete Address Box 850' Sublett Kansas 67877

Lease Name Fair Well No. C-24

Location C-NW-SE Sec. 27 Twp. 24 Rge. 33 (East)(West)

County Finney Total Depth 5360'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Daer Lease + Well Service

Address Borger Texas 79007 License No. 138

Operation Completed: Hour: 4:00 P.M. Day: 6 Month: Aug Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

They set 5310' of 5 1/2" production pipe with a plug back of 4850'. Then they perforated from 4815' to 26'. 1st plug was a cast iron plug set at 4742' with 20 lbs of cement on it. 2nd plug was a cast iron plug at 1450' with 2 lbs cement on it. 3rd plug at 1327' with 50 lbs of cement. 4th plug at 1000' with 50 lbs of cement. 5th plug 40' to 0' with 10 lbs of cement. They recovered 1327' of 5 1/2" production pipe. The plugging was accomplished by Daer Lease well service.

Amount of Surface Casing: 1934' of 8 3/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthie
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

I had all I could take care of in my area.

8-10-82

RECEIVED
STATE CORPORATION COMMISSION

Signed: Paul A. Luthie
Conservation Division Agent

AUG 10 1982
CONSERVATION DIVISION
Wichita, Kansas

INVOICED
DATE 8-13-82
INV. NO. 898-W