

1 061009

9-11-87

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 075-20,283 - 0000

SE. NE. NW, SEC. 23, T 24 S, R 39 W/E  
4030 feet from S section line  
3000 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5855

Lease Name Walters Well # 1

Operator: Wallace Oil & Gas, Inc.  
Name & Address: 50 Penn Place, Suite 850  
Oklahoma City, OK 73118

County Hamilton 87.43  
Well Total Depth 2498 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 556

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 8 a.m. Day: 10 Month: 9 Year: 19 87

Plugging proposal received from Doug Blair

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 4 1/2" at 2497' Perfs at 2314-24, 2370-78, 2402-8, 2414-18, 2420-24, 2430-40, 2476-84'  
Elevation 3246' TOC 1900'

1st plug pump 1 sx hulls and 20 sx cement to cover perfs,

2nd plug pump 20 sx cement at 1524',

3rd plug pump 50 sx cement at 600', 4th plug pump 10 sx cement at 40-0'.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 1:30 p.m. Day: 11 Month: 9 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement to cover perfs,

2nd plug pump 20 sx cement at 1524',

3rd plug pump 50 sx cement at 600',

4th plug pump 10 sx cement at 40-0'.

9-24-87  
RECEIVED  
STATE CORPORATION COMMISSION  
SEP 24 1987  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 1524' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

Signed Paul A. Luthi (TECHNICIAN)

INVOICED  
DATE 9-28-87  
INV. NO. 18274