

1 080460

15-047-19042-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- N/A

C SE SE, SEC. 27, T 25 S, R 16 (W/E)

660 feet from (S) section line

660 feet from (E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4678

Lease Name Cudney Well # A-1

Operator: Lasmo Energy Corporation

County Edwards

Name & Address P. O. Box 1365

Well Total Depth 4552 147.94 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 395

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P. O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 12:00 pm Day: 18 Month: December Year: 19 85

Plugging proposal received from Mike Gomez

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 5 1/2" at 4551' PBT 4513' Perfs at 4452-58'; 4388-92'

1st plug pump 30 sx cement to bottom

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 60 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 110 sx cement.

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:50 pm Day: 18 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 30 sx cement to bottom, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 60 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 110 sx cement.

Maximum pressure 400 psi and shut in 100 psi

Remarks: Recovered 2150' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Allied. (If additional description is necessary, use BACK of this form.)

INVOICED

(XXXXXX) observe this plugging.

STATE CORPORATION COMMISSION
12-27-85
DEC 27 1985

Signed J. A. [Signature] (TECHNICIAN)

DATE DEC 27 1985

INV. NO. 11743