

1 080458

15-047-10036-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Comp. 5-2-63

C SW SE, SEC. 27, T 25 S, R 16 W/XX  
660 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4678

Lease Name Cudney Well # B-1

Operator: Lasmo Energy Corporation  
Name & Address: P. O. Box 1365  
Great Bend, KS 67530

County Edwards  
Well Total Depth 4490 145.93 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 373

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P. O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9:00 am Day: 18 Month: December Year: 19 85

Plugging proposal received from Mike Gomez

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 5 1/2" at 4489' Perfs at 4400-06'; 4366-76'

1st plug pump 30 sx cement to bottom.

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 60 sx cement, 10 sx gel, 1 sack hulls,  
release 8 5/8" rubber plug and pump 110 sx cement.

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:15 pm Day: 18 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 30 sx cement to bottom, 2nd plug squeezed well  
with 3 sx hulls, 15 sx gel, 60 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8"  
rubber plug and pumped 110 sx cement.

Maximum pressure 50 psi and shut in 0 psi

Remarks: Recovered 2190' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DEC 27 1985

DATE

NV. NO. 11744

STATE CORPORATION COMMISSION

Signed

12-27-85  
J. A. [Signature]  
(TECHNICIAN)

DEC 27 1985