

1-120380

2-27

2380

API NUMBER 15-047-21,172-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NE NE, SEC. 27, T 25 S, R 16 W/EX

4950 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5086

Lease Name Cudney Well # 3

Operator: Pintail Petroleum

County Edwards 145.60

Name & Address 412 East Douglas

Well Total Depth 4480 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 328

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 27 Month: 2 Year: 19 90

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 4479' Perfs at 4324-26'

1st plug sand back to 4275' with 4 sx cement on top,

2nd plug pump 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,

release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10 a.m. Day: 27 Month: 2 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4275' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,

released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-650 psi and shut in 425 psi.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 2635' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 3-26-90

Signed Duane Rankin (TECHNICIAN)

INV. NO. 27718

RECEIVED STATE CORPORATION MAR 05 1990 3-5-90