

1090352

10029-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 067-01,000

C SW SE, SEC. 36, T 27 S, R 35 WXX

860' feet from S section line

1980' feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6477

Lease Name Appleman Well # 1-A

Operator: Koch Exploration Company

County GRANT 52.82

Name & Address P.O. Box 2256

Well Total Depth 1625 (Cedar Hills) feet

Wichita, KS 67201

Conductor Pipe: Size feet

Surface Casing: Size 5 1/2" feet 1500

Abandoned Oil Well Gas Well Input Well SWD Well XX D&A

Other well as hereinafter indicated

Plugging Contractor Borderline Well Service License Number 7840

Address Ulysses, KS

Company to plug at: Hour: 11:00 a.m. Day: 14 Month: May Year: 1985

Plugging proposal received from LaVerne Leiker

(company name) Koch (phone)

were: To recover as much pipe as possible and circulate hole with cement to surface.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part XXX None

Operations Completed: Hour: 4:30pm Day: 14 Month: May Year: 1985

ACTUAL PLUGGING REPORT Recovered 850' of casing. Ran back in hole with tubing and

spotted 25 sx cement at 850'. Waited for cement to set and tagged cement

at 523 feet. Then circulated 85 sx of cement from 523' to surface.

JUN 17 1985

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix, with 2% gel and 1% CaCl by Dowell Cementing.
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 6-20-85

Signed Robert Brackleton (TECHNICIAN)

INV. NO. 8640