

To: 1 030890
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

12-7-87
API NUMBER 15- 047-21,306-0000

S/2 SW SW, SEC. 31, T 25 S, R 16 W/4
410 feet from S section line
4775 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056
Operator: F.G. Holl Company
Name & Address: P.O. Box 780167
Wichita, KS 67278-0167

Lease Name Gregory Well # 1-31
County Edwards 150.48
Well Total Depth 4630 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 308

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Sterling Drilling Company License Number 5142

Address Box 129, Sterling, KS 67579

Company to plug at: Hour: 6 a.m. Day: 7 Month: 12 Year: 19 87

Plugging proposal received from Vaughn Thompson

(company name) Sterling Drilling Company (phone) 316-278-2131

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2101' Anhydrite 1118-34'

1st plug at 1170' with 50 sx cement, 2nd plug at 610' with 40 sx cement,
3rd plug at 330' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Plunout
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8:30 a.m. Day: 7 Month: 12 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1170' with 50 sx cement,
2nd plug at 610' with 40 sx cement,
3rd plug at 330' with 40 sx cement,
4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

12-8-87
RECEIVED
STATE CORPORATION COMMISSION
DEC 8 1987
CONSERVATION DIVISION
Wichita Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED
I hereby certify that I have observed this plugging.

DATE 12-8-87

Signed Steve Plunout
(TECHNICIAN)

INV. NO. 19226
12-7