

1 030749

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-047-20,465-0000

NE SE NE, SEC. 31, T 25 S, R 16 W/E
3630 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6050

Lease Name Wilson Well # 1

Operator: Kelso Casing Pulling, Inc. purchases
Name & Address from Tom Wilson - Landowner
808 Larimer
Pratt, KS 67124

County Edwards 148.53

Well Total Depth 4570 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 333

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1 p.m. Day: 21 Month: 10 Year: 19 86

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling, Inc (phone) 316-659-3165

were: 4 1/2" at 4570' Perfs at 4444-49'

1st plug sand back to 4400' and dump 4 sx cement on top of sand through bailer

2nd plug pump 3 sx hulls and 100 sx econolite.


Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 1:30 p.m. Day: 21 Month: 10 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4400' and dumped 4 sx cement on top of sand through bailer

2nd plug pumped 3 sx hulls and 100 sx econolite with 2 sx hulls mixed in.



10-23-86

Maximum pressure 300psi and shut in 100 psi

Remarks: Used econolite by Allied. Recovered 2380' 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I hereby acknowledge and observe this plugging.

Signed Steve Quenont
(TECHNICIAN)

DATE 10-23-86

INV. NO. 15219