

1 050263

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-047-21,150-0000

C NW SE, SEC. 30, T 25 S, R 16 (W)

1980 feet from N/S section line

1980 feet from N/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name Ellis Well # 1-30

Operator: Texas Energies, Inc.

County Edwards

Name & Address P. O. Box 947

Well Total Depth 4550 \$ 147.88 feet

Pratt, KS 67124

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 465

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A^X _____

Other well as hereinafter indicated _____

Plugging Contractor Big Kat Drilling License Number 5839

Address Box 18154, Wichita, KS 67218

Company to plug at: Hour: 8:00 pm Day: 23 Month: June Year: 19 84

Plugging proposal received from Jerry Hugh

(company name) Big Kat (phone) 316-684-4433

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1130' with 50 sx cement

2nd plug at 400' with 40 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Richard M. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 10:15 pm Day: 23 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1130' with 50 sx cement, 2nd plug at 400' with 40 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 29 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton
(if additional description is necessary, use BACK of this form)

CONSERVATION DIVISION
WICHITA, KANSAS

INVOICED

(copy did not) observe this plugging.

Signed Richard M. Lacey
(TECHNICIAN)

DATE 7-5-84

INV. NO. 2285