

To: 1040954 4-26  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. **PLUGGING SECTION**  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-047-20,498-0000  
SE SE SW, SEC. 34, T 25 S, R 16 W/2  
330 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056  
Operator: F.G. Holl Company L.L.C.  
Name: \_\_\_\_\_  
Address P.O. Box 780167  
Wichita, KS 67278-0167

Lease Name Cudney C Well # 1-34  
County Edwards  
Well Total Depth 4525 147.06 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 412

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SMD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pratt Well Service License Number 5893  
Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 1:45 p.m. Day: 26 Month: 4 Year: 19 95

Plugging proposal received from Kenny Gates  
(company name) Pratt Well Service (phone) 316-672-2531

work: 4 1/2" at 4520' w/150 sx cement, PBD 4405', Perfs at 4370-74'  
1st plug sand back to 4280' and dump 4 sx cement on top of sand bridge through bailer,  
2nd plug pump down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,  
100 lbs. hulls, release 8 5/8" wiper plug and pump 150, sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:15 p.m. Day: 26 Month: 4 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back to 4280' and dumped 4 sx cement on top of sand  
bridge through dump bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx  
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 500 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2700' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

**INVOICED**

DATE 5-2-95  
INV. NO. 42724

Signed Stephen J. Pfeifer  
(TECHNICIAN)

KANSAS RECEIVED  
CORPORATION COMMISSION  
MAY 07 1995  
CONSERVATION DIVISION  
WICHITA, KS  
3-1-95