

1 060181

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C/2
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-047-21,140 - 0000
NE SE, SEC. 34, T 25 S, R 16 ~~WXX~~
2310 feet from ~~X~~/S section line
660 feet from ~~X~~/E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 8061

Lease Name T. L. Wilson Well # 3
County Edwards

Operator: Oil Producers, Inc. of Kansas
Name & Address P. O. Box 8647
Wichita, KS 67208

Well Total Depth 4515 146.73 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 385

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11:30 am Day: 23 Month: February Year: 19 84

Plugging proposal received from Bob Brenneman

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2 set at 4515 PBDT 4501 Perfs 4424-32

1st plug sand back to 4375 with 4 sx cement dumped on top of sand

2nd plug squeeze through head with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel,

1 sack hulls and release 8 5/8" rubber plug and pump additional 150 sx cement

Maximum pressure 200# and shut-in pressure 0

Plugging Proposal Received by Paul A. Luthis
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 1:15 pm Day: 23 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2 set at 4515 PBDT 4501 Perfs 4424-32

1st plug sand back to 4375 with 4 sx cement dumped on top of sand 2-29-84

2nd plug squeeze through head with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel,

1 sack hulls and released 8 5/8" rubber plug and pumped additional 150 sx cement.

Maximum pressure 200# and shut-in pressure 0

Remarks: They recovered 3811' of 4 1/2. Use 60/40 Pozmix 2% gel 3% cc. by Allie
(if additional description is necessary, use BACK of this form.)

(d) of ~~(c)~~ observe this plugging.

INVOICED

DATE 3/7/84

INV. NO. 0564

Signed Paul A. Luthis
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
FEB 29 1984
CONSERVATION DIVISION
Wichita, Kansas