

To: 1 120895 2-24
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- NA 15-047-20673-0001

SE SW SE, SEC. 34, T 7 S, R 16 W/E
330 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Lease Name TL Wilson Well # 2

Operator: Oil Producers, Inc. of Kansas

County Edwards

Name & Address P.O. Box 8647

Well Total Depth 4479 145.57 feet

Wichita, KS 67208

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 454

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor DS&W Well Servicing, Inc. License Number 6901

Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 9 a.m. Day: 24 Month: 2 Year: 1994

Plugging proposal received from Joe Strube

(company name) DS&W Well Servicing, Inc. (phone) 316-587-3361

vers: 4 1/2" at 4479' w/175 sx cement, PBD 4477', Perfs at 4440-60'

1st plug sand back to 4390' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper

plug and pump 125 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 a.m. Day: 24 Month: 2 Year: 1994

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 4390' and dumped 4 sx cement on
top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-500 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2300' of 4 1/2" casing
(if additional description is necessary, use BACK of this form.)

observe this plugging.

DATE MAR 09 1994

Signed [Signature]
(TECHNICIAN) CONSERVATION DIVISION
Wichita, Kansas

INV. NO. 40082