

1 120188

DEC 16 1988 15-047-20381-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-Docket #D-19,445

SW NW SE, SEC. 29, T 25 S, R. 18 W/EX

1830 feet from S section line

2130 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Lease Name Wilson Well # 2-29

Operator: Murfin Drilling Company

County Edwards 153.50

Name & Address 250 North Water, Suite 300

Well Total Depth 4723 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 496

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SHD Well  D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 10:30 a.m. Day: 16 Month: 12 Year: 19 88

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 3248' PBD 3205' Perfs at 2610-16'

1st plug sand back to 2560' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 120 sx cement

RECEIVED  
STATE CORPORATION COMMISSION  
12-21-88

Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1 p.m. Day: 16 Month: 12 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 2560' and dump 4 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-700 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1704' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED

Signed Quam Rankin (TECHNICIAN)

DATE DEC 22 1988

INV. NO. 23439