

00321

TO: STATE CORPORATION COMMISSION API NUMBER 15-119-20,951-0060 200'W C N/2 NE SEC. 34, T 32 S, R 29 W

CONSERVATION DIVISION - PLUGGING SECTION 4620 FEET FROM SOUTH SECTION LINE WICHITA STATE OFFICE BLDG., 130 S. MARKET 1520 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME ATKINSON WELL # 2-34

TECHNICIAN'S PLUGGING REPORT COUNTY MEADE 12/1 190.13

OPERATOR LICENSE # 30128 WELL TOTAL DEPTH 5850 FEET

OPERATOR: KENNETH S WHITE PRODUCTION CSG: SIZE 4 1/2" @ 4922' WITH 150 SX

NAME AND ADDRESS 260 N ROCK ROAD, SUITE 240 SURFACE CASING: SIZE 8 5/8" @ 1531' WITH 625 SX WICHITA, KS 67206

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC LICENSE NUMBER 31151

ADDRESS RT. 1, BOX 49BA, TYRONE, OK 73951-9731

COMPANY TO PLUG AT: HOUR: 10:00 AM DAY: 12 MONTH: 01 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM DON HORTON

(COMPANY NAME) SARGENT & HORTON PLUGGING, INC (PHONE) 580-854-6515

WERE: PERFS AT 4560-4570

1ST PLUG PUMP 20 SX CEMENT WITH 100# HULLS AT 4850'. 2ND PLUG SPOT 50 SX CEMENT AT 1560'.

3RD PLUG SPOT 25 SX CEMENT AT 700'. 4TH PLUG SPOT 10 SX CEMENT FROM 40' TO SURFACE.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 4:00 PM DAY: 12 MONTH: 01 YEAR: 2000

ACTUAL PLUGGING REPORT

1ST PLUG PUMP 20 SX CEMENT WITH 100# HULLS AT 4850'. 2ND PLUG SPOT 50 SX CEMENT AT 1560'.

3RD PLUG SPOT 25 SX CEMENT AT 700'. 4TH PLUG SPOT 10 SX CEMENT FROM 40' TO SURFACE.

INVOICED

DATE 1/19/00

WV. NO. 061143

RECEIVED STATE CORPORATION COMMISSION

JAN 18 2000

1-18-00

CONSERVATION DIVISION Wichita, Kansas

REMARKS: USED COMMON CEMENT BY SARGENTS. RECOVERED 3005' of 4 1/2" CASING. (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED

Gary Winters (TECHNICIAN)

FORM CP-2/3

Handwritten initials and signature in a circle.