

To: 1 090700
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- NA 15-057-10016-0000
C NE SW, SEC. 26, T 27 S, R 24 W/X
1980 feet from S section line
3304 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License / 5817

Lease Name L.A. McCoy Well # 1
County Ford

Operator: Benson Mineral Group, Inc.
Name:
Address 1560 Broadway, Ste. 1900
Denver, CO 80202

Well Total Depth 5140 167.05 feet
Conductor Pipe: Size feet
Surface Casing: Size 10 3/4 feet 554

Abandoned Oil Well Gas Well X Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Benson Mineral Group, Inc. License Number 5817
Address 1560 Broadway, Ste. 1900, Denver, CO 80202

Company to plug at: Hour: 9 a.m. Day: 20 Month: 6 Year: 19 96

Plugging proposal received from Phil Kempton
(company name) Benson Mineral Group, Inc. (phone) 303-853-3541

Work: 4 1/2" at 5139' w/150 sx cement, PBTD 2700', Perfs at 2620-30', DV at 2888' w/180 sx cmt.
1st plug pump 2 sx hulls and 20 sx cement at 2600',
2nd plug shoot casing at 918' and spot 80 sx cement,
3rd plug pull to 580' and spot 75 sx cement,
4th plug pull to 30' and spot 15 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:30 a.m. Day: 20 Month: 6 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 20 sx cement at 2600',
2nd plug shot casing at 918' and spotted 80 sx cement,
3rd plug pulled to 580' and spotted 75 sx cement,
4th plug pulled to 30' and spotted 15 sx cement,
Stayed full.

RECEIVED
KANSAS CORPORATION COMMISSION
6-28-96
JUN 28 1996

Remarks: Used common cement by BMG. Recovered 918' of 4 1/2" casing.
(If additional description is necessary, use BACK of THIS FORM.)

INVOICED

DATE JUL 03 1996
INV. NO. 45919
6-20

Signed [Signature]
(TECHNICIAN)