

To: 1 090699
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- NA 15-057-00052-00-00
NE SE SW, SEC. 26, T 27 S, R 24 W/E
949 feet from S section line
2985 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5817
Operator: Benson Mineral Group, Inc.
Name:
Address 1560 Broadway, Ste. 1900
Denver, CO 80202

Lease Name Barngrover Well # 1 (Tenneco #1)
County Ford
Well Total Depth 5238 ^{170.23} feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 560

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Benson Mineral Group, Inc. License Number 5817
Address 1560 Broadway, Ste. 1900, Denver, CO 80202

Company to plug at: Hour: 1 p.m. Day: 20 Month: 6 Year: 19 96

Plugging proposal received from Phil Kempton
(company name) Benson Mineral Group, Inc. (phone) 303-863-3541

work: 5 1/2" at 5236' w/175 sx cement, PBTD 5189', Perfs at 5063-72, 4874-4883', DV at 2200' w/
1st plug run tubing to 4800' and spot 2 sx hulls and 25 sx cement,
2nd plug perforate casing at 950' and pump 10 sx gel and 80 sx cement,
3rd plug shoot pipe at 600' and pump in 75 sx cement,
4th plug top off with cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 2:45 p.m. Day: 20 Month: 6 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug ran tubing to 4800' and spotted 2 sx hulls and 25 sx cement,
2nd plug perforated casing at 950' and pumped in 10 sx gel and 80 sx cement,
3rd plug shot pipe at 600', pulled one joint to 570', and pumped in 75 sx cement,
4th plug topped off with 15 sx cement. Stayed full.

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 28 1996

Remarks: Used common cement by BMG. Recovered 600' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form)
OBSERVATION DIVISION
WICHITA, KS

1 (copy) ~~XXXXXX~~ observe this plugging.

DATE JUL 03 1996

Signed _____
(TECHNICIAN)

INV. NO. 45920
6-20