

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20924-00-00
Spot: W2NWSE Sec/Twnshp/Rge: 22-32S-30W
1980 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: FOX Well Number: 1-22
County: MEADE Total Vertical Depth: 6103 feet

Operator License No.: 30129
Op Name: EAGLE CREEK CORPORATION
Address: 150 N. MAIN, STE 905
WICHITA, KS 67202

Conductor Pipe Size: 20 feet: 56 WITH 7 YDS CMT
Production Casing Size: 4.5 feet: 6067 WITH 250 SX CMT
Surface Casing Size: 8.625 feet: 1627 WITH 585 SX CMT
#198³⁵

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/18/2003 10:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PUMP 20 SX CMT & 100# HULLS. PLUG AT 1650' WITH 50 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/18/2003 2:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:
PBTD 6067. PERFS AT 5540-44'. PUMP 100# HULLS WITH 20 SX CMT. LOAD HOLE & PRESSURE TO 1000 PSIG. 1ST PLUG PULL OUT OF HOLE TO 1650'. LOAD HOLE & PUMP 50 SX CMT. DISPLACE WITH MUD. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 550'. LOAD HOLE & PUMP 40 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

RECEIVED
OCT 14 2003
KCC WICHITA

Remarks: USED COMMON CMT BY SARGENT & LILLARD. RECOVERED 2810' OF 4 1/2" CASING.
Plugged through: CSG

District: 01

RECEIVED
SEP 30 2003
KCC Dodge City

Signed Jim Holland (TECHNICIAN)

INVOICED
DATE 10-14-03
INV. NO. 2004060613

Form CP-213