

1050431

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15 - Not Available
SW NW 22, SEC. 21, T 32 S, R 30 W/E
3300 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7135
Operator: Wendell B. Fox
Name & Address: Box 55
Plains, KS 67869

Lease Name Wendell B. Fox Well # 1
County Meade 198.58
Well Total Depth 6110 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1541 ✓

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Reeves & Wilson License Number 6083

Address 3401 Willow West, Woodward, OK 73801

Company to plug at: Hour: 6:00 pm Day: 10 Month: January Year: 19 85

Plugging proposal received from Wendell B. Fox

(company name) Wendell B. Fox (phone) 316-563-7349

were: 4 1/2" set at 6110' Spot cement through 4 1/2" casing with heavy mud between plugs

1st plug at 4622' with 10 sx cement (above top perms)

2nd plug at 1560' with 50 sx cement

3rd plug at 700' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' --- cement to surface with 10 sx cement

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 9:00 pm Day: 10 Month: January Year: 19 85

ACTUAL PLUGGING REPORT 4 1/2" set at 6110'

1st plug at 4622' with 10 sx cement, 2nd plug at 1560' with 50 sx cement, 3rd plug at 700'

with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at surface with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
1-15-85
JAN 15 1985

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Recovered 1564' 4 1/2" casing. Used common cement by Reeves & Wilson
(If additional description is necessary, use BACK of this form.)

(operator) observe this plugging.

INVOICED

DATE 1-18-85

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 6592

FEB 18 1985