

1 080577

DEC 9 1986

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-20,636-A-0001
NW NE, SEC. 20, T 32 S, R 10 W/E
4620 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6006

Lease Name McKeever Well # 1

Operator: Molz Oil Company
Name & Address R.R. 2, Box 54
Kiowa, KS 67070

County Barber 154.38

Well Total Depth 4750 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 262

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10 a.m. Day: 9 Month: 12 Year: 1986

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4748' PBD 4720' Perfs at 4684-87' Elevation 1465'GL

1st plug sand back to to 4630' and dump 5 sx cement on top of sand through bailer,

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release plug and pump 100 sx cement.

Plugging Proposal Received by Jack Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:45 a.m. Day: 9 Month: 12 Year: 1986

ACTUAL PLUGGING REPORT 1st plug sanded back to 4630' and dumped 5 sx cement on top of sand through bailer,

2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 900 psi and shut in 550 psi.

Remarks: Used 60/40 Pozmix by B.J. Titan. Recovered 3600' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
(If no invoice is observed this plugging.

DATE 12-17-86.

Signed J. B. [Signature]
(TECHNICIAN)

INV. NO. 15657