

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 20 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name National Coop. Refg. Assn ^{of} Irving J. Gotsche

Complete Address Box 6 Great Bend, Ks

Lease Name Floyd Gudney Well No. 1

Location C NE/SW Sec. 27 Twp. 25 Rge. 16 (E) (W) W

County Edwards Total Depth 4428

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Ralph Gomstock Casing Pulling Inc.

Address Stafford, Ks License No. 490

Operation Completed: Hour 1:00 PM Day 16 Month 12 Year 1971

The above well was plugged as follows:
401 ft 8 5/8 surface pipe cement circulated. 4427 ft 5 1/2 long string
cemented with 100 sacks. Top perf. 4372 ft. Sand back to 4350 ft.,
5 sacks cement with bailer. Pulled 3090 ft 5 1/2. Pump 2 sacks hulls,
15 sacks gel. 100 sacks cement to surface.
Pumped by Globe Cementing Co. Great Bend, Ks

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 1-6-72
INV. NO. 4845-W