

15-067-00022-0000

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 17 1964  
2-17-64  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name R.W. Lange

Complete Address: Box 1034 Garden City, Kansas

Lease Name Pollyanna Well No. 1

Location SE SE Sec. 36 Twp. 27S Rge. (E) (W) 35

County Grant Total Depth 5659'

Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A X

Other well as hereafter indicated:

Plugging Contractor: Sargent Casing Pulling Service

Address: Liberal, Kansas License No. 511

Operation Completed: Hour 5 PM Day 12 Month 2 Year 64

The Above well was plugged as follows:

8 5/8"-670' Circulated w/cement. 5 1/2"-4650' Cemented.

Plug back w/baker bridge plug at 3050' DV tool at 2900'

Perforations 3035' to 2929' Plug bottom w/20 Sax.cement 3050' to 2829'

Mud 2829' to 650' Spotted 10 Sax.cement 650' to 550'

Mud 550' to 50' Plug, 5 Sax.cement 50' to 0

Cut pipe off 5' below ground level, weld cap on pipe. No pipe pulled.

Company Pump.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 2/18/64

INV. NO. 8659-w