

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

7-5-62
RECEIVED
STATE CORPORATION COMMISSION

JUL 5 1962

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Finger Oil Co.
Complete Address: 1020 Central Building, Wichita, Kansas
Lease Name Henshaw Well No. #22
Location SW SW NE Sec. 34 Twp. 25 Rge. (E) (W) 16
County Edwards Total Depth 4442'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated: Abandoned
Plugging Contractor: Knight Casing Pulling Co.
Address: Box 304 Chase, Kansas License No. 436
Operation Completed: Hour 12: Noon Day 4th Month July Year 1962

The Above well was plugged as follows:

Top perforation at 4036' . Hole filled with sand to 4030' .
5 sacks cement as plug. 405' of 8 5/8" surface pipe. Hole filled
with heavy drilling mud to 300' . Rock bridge to 290' . 25 sacks
cement as plug. Filled to 40' with heavy drilling mud. Second bridge
and 10 sacks cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 7-6-62
INV. NO. 5318-W

Signed: Herman Justice
Well Plugging Supervisor